



Proposal

Municipality of the District of Argyle

Attn: Kyle Boudreau

September 15, 2021

Proposal #12-79

To relocate existing generator

To include:

- 8'x8'x8" concrete pad complete with 15M rebar at 12" centres in both directions.
- 3 x 5" Steel bollards with caps to be filled with concrete.
- A new oil tank with connections to match existing installation and removal of existing tank.
- Crane to relocate generator from municipal office to treatment plant on Courthouse Rd.
- New electrical cabling from transfer switch to generator. Including trenching from building to generator pad.
- Reconfigure electrical service to allow for placement of the transfer switch, including addition of a service rated disconnect switch on exterior of the building.

We propose here by to furnish labor and materials – complete in accordance with above specifications, for the sum of: Total cost for job on labor and materials of \$10,365.04 plus HST.

All materials are guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra cost will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents, or delays beyond our control. Owner to carry fire, windstorm and other necessary insurance. Our workers are fully covered by Workers Compensation Insurance.

Authorized Signature *Jonathan LeBlanc*

Note: This proposal may be withdrawn by us if not accepted within 30 days.

Acceptance of Proposal

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Date of Acceptance _____

Signature _____